

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--:                          | LOCATED IN--:                          | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>44</u> N. S., R. <u>23</u> E. W. | <u>M-3, M-4</u>    |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. S., R. _____ E. W.         | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W.         | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |  |                    |
| 5. PRIVATE CLAIMS _____                    |  |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 20 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- M-3 N.E. Section Corner - Section 12; Wood Post, Cedar 12 - S60°E - 8 lks.; Cedar 14 - N60°W - 20 lks.; Bl. Ash 12 - N30°E - 61 lks.
- M-4 East 1/4 corner - Section 12; Wood Post, Hemlock 16 - S39°E - 40 lks.; Hemlock 12 - N31°W - 24 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- M-3 Found both cedar O.B.T.'s - N.W. one showing both upper and lower face - scribing weathered off, both trees down and rotted. Bearings and distances good. Distance (94 lks.) north to creek is good.
- M-4 Found stumps of both hemlock, O.B.T.'s showing part of lower face partially overgrown. Both stumps in poor condition - no scribe marks remain. Bearings and distances good.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL 1" pipe, 4" aluminum cap
- M-3 13" Cedar - S45°E - 35.9'; 4" Cedar - S16°E - 26.9'; 5" Cedar - S53°W - 41.7'; 15" Cedar - N71°E - 74.6'.
- M-4 4" Cedar - S55°W - 18.1'; 8" Hemlock - N9°E - 18.3'; 8" Hemlock - N60°E - 23.1'; 10" Hemlock - S37°E - 4.8'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 1-22-80  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558