

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>L-7, M-7, M-8</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on October 22 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 North $\frac{1}{4}$ corner - Section 24; Wood Post, Cedar 13 - S14°W - 22 lks.; Cedar 12 - N58°W - 20 lks.; probably destroyed by road and power line construction.
- M-7 N.E. section corner - Section 24; Wood Post, Birch 17 - S34°W - 45 lks.; Hemlock 12 - N40°E - 35 lks.; Tam. 12 - N52°W - 28 lks.; Birch 15 - S39°W - 46 lks.
- M-8 East $\frac{1}{4}$ corner - Section 24; Wood Post, Fir 10 - S29°W - 21 lks.; Fir 12 - N13°E - 20 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 Set M.P.O.L. between the N.E. and N.W. section corners of Section 24.
- M-7 Set by single proportionate measure using section corners one mile north and one mile south. Measurements to $\frac{1}{4}$ corner $\frac{1}{2}$ mile east and section corner one mile west are reasonable. Buried monument in the north wheel track of E-W road. Placed stones on top to protect it from traffic.
- M-8 Set M.P.O.L. between the N.E. and S.E. section corners of Section 24

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 1" pipe, 4" aluminum cap buried in centerline of road; 6" Cedar - N30°W - 52.1'; 4" Cedar - S43°E - 56.2'; 4" Cedar - S12°W - 47.8'; 7" Cedar - N44°W - 51.5'.
- M-7 1" pipe, 4" aluminum cap buried in E-W road; 3" Cedar - N7°W - 45.9'; 6" Cedar - S19°W - 36.7'; 6" Spruce - S31°E - 65.0'; Power pole - S51°E - 33.2'.
- M-8 1" pipe, 4" aluminum cap; 6" Maple - S89°E - 9.9'; 4" Maple - S26°E - 17.4'; 4" Maple - N71°W - 17.8'; 6" Y. Birch - N1°E - 32.6'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 1-26-81 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558