

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>K-1</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	, T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on October 23 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-1 N.E. section corner - Section 1; Wood Post, Birch 18 - N32°E - 47 lks.; Do. 9 - N30°W - 13 lks.; Fir 10 - S55°E - 39 lks.; Fir 9 - S28°W - 31 lks.
- 1 West 1/16 corner on the north section line of Section 1; not previously established.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-1 Set by projecting a straight line across the N. 1/4 corner and the N.E. section corner of Section 1. Measurements proportioned to G.L.O. record between the N. 1/4 corner of Section 1 and the N.W. corner of Section 2. This position fits much better measuring to corners one mile north and 1/2 mile south, than a straight line between the N. 1/4 corner of Section 1 and the N.W. corner of Section 2 does.
- 1 Set M.P.O.L. between the N.W. section corner and the N. 1/4 corner of Section 1

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-1 1" pipe, 4" aluminum cap; 3" Spruce - S75°W - 12.5'; 4" Y. Birch - N30°W - 12.3'; 6" Maple - N62°E - 15.3'; 6" Maple - S20°E - 10.95'.
- 1 1" pipe, 4" aluminum cap; 7" Cedar - N24°E - 76.9'; 7" Hemlock - N74°E - 45.0'; 8" Hemlock - S30°W - 51.4'; 5" Y. Birch - N58°W - 37.8'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 1-26-81

CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558