

Marquette

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>K-6</u>
2. PROPERTY CONTROLLING IN SECTION <u>14</u>	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>7, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 2 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-6 East  $\frac{1}{4}$  corner, Section 14; Wood Post, Birch 15 - N47°E - 18 lks.; Maple 11 - S27° - 25 lks.
- 7 North 1/16 corner on the east section line - Section 14; not previously established.
- 14 South 1/16 corner on the east section line - Section 14; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-6 Set M.P.O.L. between the northeast and southeast section corners of Section 14.
- 7 Set M.P.O.L. between the east  $\frac{1}{4}$  corner and the northeast section corner of Section 14.
- 14 Set M.P.O.L. between the east  $\frac{1}{4}$  corner and the southeast section corner of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap.
- K-6 14" W. Spruce - N15°W - 13.2'; 5" R. Maple - N25°E - 8.6'; 16" Hemlock - S42°E - 47.2'; 6" B. Cherry - S25°W - 6.0'.
- 7 6" Cedar - S81°W - 13.6'; 15" Cedar - N41°W - 13.9'; 9" Cedar - N21°E - 7.2'; 5" Balsam - S51°E - 17.5'.
- 14 9" Cedar - N34°W - 26.0'; 7" Cedar - N40°E - 23.4'; 4" Y. Birch - S23°E - 21.5'; 5" B. Ash - S44°W - 21.5'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 8-26-80  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558