

E. Mich.  
8-26-80

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>I-1, I-2</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on June 23 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-1 N.W. Section corner - Section 2, U.S. G.S. record; U.S. G.S. monument "TT6S" is 18 north and 27' west of the corner of sections 34 & 35, T45N-R23W and Sections 2 & 3, T44N-R23W.

I-2 West  $\frac{1}{4}$  corner - Section 2; Wood Post, Spruce 11 - S75°W - 6 lks.; Spruce 8 - N72°E - 39 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-1 Set 27' east and 18' south of U.S. G.S. monument "TT6S" as described in the U.S. G.S. notes for their monument. Fits stream calls both north and south very well and falls 3 feet west of the centerline of a N-S County Road (County Road 533).

I-2 Set on line between the S.W. and N.W. section corners of Section 2 and prop. measurement to G.L.O. record measurement fits G.L.O. calls to streams north and south very well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 1" pipe, 4" aluminum cap buried in road; 10" Cedar - S29°W - 58.5'; 9" Cedar - S71°W - 41.2'; U.S. G.S. Mon. - N55°W - 32.65'; 9" Hemlock - S73°E - 38.3'; Centerline road - East - 3'.

I-2 1" pipe, 4" aluminum cap buried in road; 6" Cedar - N81°W - 34.8'; 6" Cedar - N44°W - 55.7'; 6" Cedar - N26°E - 65.5'; 8" Spruce - S63°E - 29.8'; Center N-S road - West - 3'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 8-26-80  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558