

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>44</u> N. S., R. <u>23</u> E. W.	<u>I-3, I-4, K-4</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 9 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- I-3 N.W. Section corner - Section 11; Wood Post, Hemlock 14 - N62⁰E - 31 lks.; Fir 9 - N55⁰W - 15 lks.
 - I-4 West $\frac{1}{4}$ corner - Section 11; Wood Post, Sugar 11 - East - 34 lks.; Do 12 - N61⁰W - 32 lks.
 - K-4 East $\frac{1}{4}$ corner - Section 11; Wood Post, Birch 9 - N32⁰W - 24 lks.; Cedar 10 - S36⁰E - 30 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- I-3 Set on line and prop. measurement to G.L.O. record mea. between W. $\frac{1}{4}$ corner of Sec. 11 and the N.W. corner of Sec. 2 which falls approximately in the centerline of N-S County Road 533. Stream call north fits very well.
 - I-4 Set in line with old fence south and centerline of road west and north. Measurements north and south to nearest est. corners fit well.
 - K-4 Set M.P.O.L. between the N.E. and S.E. section corners of Section 11.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-3 1" pipe, 4" aluminum cap buried in road; 10" Y. Birch - N62⁰W - 36.3'; 10" Maple - S52⁰W - 33.9'; 6" Cedar - S51⁰E - 58.4'; 12" Cedar - N52⁰E - 63.1'.
 - I-4 1" pipe, 4" aluminum cap; 17" Hemlock - S60⁰E - 72.3'; 7" Y. Birch - S18⁰W - 24.9'; 6" Twin Maple - N41⁰W - 97.2'; 11" Y. Birch - S75⁰E - 62.3'.
 - K-4 1" pipe, 4" aluminum cap; 6" Y. Birch - S15⁰E - 11.2'; 6" Red Maple - S87⁰W - 14.1'; 4" Cedar - N1⁰W - 30.4'; 6" Cedar - N56⁰W - 29.0'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 8-26-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558