

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 24 W.

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sec. 's 2-3-10-11

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 11" Soft Maple ----- S 12° W ----- 53 links

"S 10 NBT"

9" Elm ----- S 44° E ----- 56 links

"S 11 NBT"

18" W. Spruce ----- N 50° W ----- 21 links

"S 3 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner in old fence corner. Fence running north and west.

Evidence of use: old cruisers register tree with names and dates about 25 years old.

Testimony of Henry Block, a local resident.

Corner being used in this position for many years.

Corner checks well with corners in all directions.

Corner lies in SE corner of cleared field.

SURVEYORS SEAL

SIGNED Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 11/12/57