

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 24 W.

----- Marquette -----

----- COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 2-3

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" B. Spruce N 56° E 42 links
"1/4 S NBT"

8" B. Spruce S 53° E 63 1/2 links
"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner by proportionate measure and on line between section corners. No evidence of original corner. 1/4 corner lies on south end of small clearing.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/12/57
REGISTERED LAND SURVEYOR