

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. <u>24</u> R. <u>W.</u>	E-10, F-9, G-10
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 9 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| <p>E-10 Woodpost:
 Tamarack 11" N57°E 31 links
 Tamarack 10" N80°W 45 links
 Subsequent monument: Woodpost</p> <p>F-9 Woodpost:
 Tamarack 8" N10°E 17 links
 Tamarack 7" S20°E 4 links
 Subsequent monument: Scribed woodpost</p> | <p>G-10 Woodpost:
 B. Ash 6" S62°E 47 links
 Cedar 12" S84°W 26 links
 Subsequent monument: 3/4" iron pipe and rotted woodpost</p> |
|---|---|

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-10** This corner was replaced from old woodpost in proper position with bearings and distances to two Tamarack B.T.'s.
- F-9** This corner was replaced from scribed woodpost. Signature tree near with dates back to 1913 on the blazed trees near.
- G-10** This corner was set from original cedar witness: cedar 12 S84°W 26 fallen over but in good condition. County witness in excellent condition. 3/4" iron pipe and rotted post bottom in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All: 1" iron pipe with 1/4" aluminum cap. All bearings are magnetic.

E-10	9" Cedar	(1/8)	(NBT)	N52°E	22.6'
	9" Cedar	(1/8)	(NBT)	S07°W	18.2'
F-9	7" Cedar	(1/8)	(NBT)	S85°E	8.6'
	7" Cedar	(NBT)	Signature tree	N82°W	3.0'
G-10	5" B. Spruce	(1/8)	(NBT)	N27°W	5.1'
	8" B. Spruce	(1/8)	(NBT)	N85°E	10.6'
	County Witness: 9" Cedar			N65°E	19.8'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 6-17-74
MICHIGAN REGISTERED LAND SURVEYOR (Frank J. Bray) (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575