

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 N. S., R. 24 E. W.	H-3, G-2 & G-1
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 19, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- H-3 - South 1/4 corner of Sec. 3; wood post - Lynn 17" - S23E - 17 Lks., sugar 9" - N56W - 12 Lks.
  - G-2 - West 1/4 corner of Sec. 3; wood post, B. Ash 6-S66W - 17 Lks., B. Ash 7 - N35E - 23 Lks.
  - G-1 - N.W. Sec. Cor. of Sec. 3, Marquette County Road Commission records. Set Iron pipe from old cedar B.T.'s fallen & decayed. N.B.T.s Black Ash 10" - N28W - 28.0', Black Ash 10" - S44W - 22.2'.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- H-3 - Set M.P.O.L. between the S.E. and S.W. section corners of Section 3.
  - G-2 - Set on line and proportionate measurement to G.L.O. record between the N.W. and S.W. section corners of Section 3. Corner falls 8 links south of small stream as recorded in the notes of the original government survey.
  - G-1 - Found 1" pipe-dead Black Ash stub 20' tall - N28W - 28.0 ft. with blazes and scribing. No sign of O.B.T.s at this time. Replaced pipe with D.N.R. Mon.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- H-3 - D.N.R. Mon.; 9" H. Maple - S52°W - 28.6'; 16" H. Maple - S28°E - 30.15'; 14" Y. Birch - N68°E - 36.1'; 6" H. Maple - N46°W - 47.15'.
  - G-2 - D.N.R. Mon.; 6" Cedar - S85°E - 69.7'; 5" Bl. Ash - S22°W - 2.15'; 9" Spruce - S78°W - 20.0'; 7" Spruce - N75°W - 4.6'.
  - G-1 - D.N.R. Mon.; 5" Balsam - S51°W - 19.7'; 4" Bl. Ash - N49°W - 11.1'; 4" Bl. Ash - N2°E - 9.1'; 4" Bl. Ash - N66°E - 11.2'.

SIGNED BY David B. Babbitt DATE 12-16-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET