

MARQUETTE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 44 N. S., R. 24 W.	G-3, H-1
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 5, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-3 - S.W. Sec. Cor. of Section 3; From Marquette County Rd. Comm. records old B.T. - Cedar 11" - N78°E - 18 links has fallen and decayed; set iron pipe and new B.T.s & Cedar Post; Black Ash 14" - S75°E - 6.8'; Balsam 4" - N68°W - 14.6'.

H-1 - N 1/4 Cor.; Mich. State Hwy. Dept. found wood stake set - 1" iron pipe; 4" Balsam - N30°E - 9.03'; 4" Cedar - Due E. 11.50'; 8" Hemlock - S50°E - 8.12'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-3 - Found iron pipe & signature tree with legible dates as old as 1943. Co. Road Comm. N.B.T.s in place but in very poor condition. The 14" Black Ash - S75°E - 6.8' is a badly rotted stump and the 4" Balsam N68°W - 14.6' is also a rotted stump but still showing some axe marks and over-growth.

H-1 - Set M.P.O.L. Betw. the N.E. and N.W. Sec. Cors. of Sec. 3; found 1" pipe 56.3' - S10°E - of this Mon. which the Mich. State Hwy. Dept. set from a stake of unknown origin. Said pipe does not agree with Mons. set from original bearing trees 1/2 mile West and 1/2 mile East. Because of this and its questionable origin this pipe was not accepted as being the true 1/4 Cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 - 1" pipe, 4" aluminum cap; 9" Cedar - S84°W - 6.6'; 8" B. Spruce - N51°W - 5.6'; 8" Cedar - N9°W - 15.3'; 8" Cedar - S4°E - 55.5'.

G-3 - 1" pipe, 4" aluminum cap; Cedar 4" - S50°W - 14.7'; Cedar 5" - N70°E - 17.5'; Cedar 3" - N32°E - 19.7'; Cedar 3" - N21°W - 12.3'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(BEAL)

FOR STATE AND UNITED STATES AGENCIES: