

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**MARQUETTE**

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 44 N. S., R. 24 W.	H-2
2. PROPERTY CONTROLLING IN SECTION	3, T. 44 N. S., R. 24 E. W.	3
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 5, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-2 - C. 1/4 Cor. of Sec. 3; Marquette Co. Road Comm. center Cor. - Circ. iron rod - Dry Cedar 7" - N31°E - 15.7'; Cedar 8" - N12°W - 31.8'.
- 3 - N 1/16 Cor. on the West Sec. line of Sec. 3; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-2 - Set at the intersection of the N-S and E-W 1/4 lines of Sec. 3. Found iron rod set by Marquette Co. Rd. Comm. 18.3' N39°E of this Mon. Found error in Road Comm. computations plus incorrect method used.
- 3 - Set on line and proportionate distance between the West 1/4 Cor. and the N.W. Sec. Cor. of Sec. 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-2 - D.N.R. Mon.; 6" Cedar - S56°W - 22.3'; 4" Cedar - N74°W - 5.4'; 3" Cedar - N25°E - 2.0'; 3" Cedar - S82°E - 21.5'.
- 3 - D.N.R. Mon.; 6" Cedar - N22°W - 27.7'; 6" Cedar - S66°W - 5.95'; 9" Cedar - N72°E - 4.8'; 7" Cedar - S13°E - 14.55'.

SIGNED BY

*David B. Babbitt*

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)