

LAND CORNER RECORDATION CERTIFICATE

MARQUETTE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION	3, T. 44N N. S., R. 24W E. W.	2, 6, 9
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/11/83, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2 - E 1/16 Cor. on the N. Sec. line of Sec. 3; not previously established.
- 6 - NE 1/6 Cor. (Ctr. of the N.E. 1/4) of Sec. 3; Marquette Co. Rd. Commission; Circ. iron pin & Tam. post; W. Pine 5" - N25 1/2° W - 6.8'; Balsam 10" - S47° E - 5.4'.
- 9 - East 1/16 Cor. on the E-W 1/4 line of Sec. 3; Marquette Co. Rd. Comm.; Circl. iron rod on trail; Balsam 3" - N87° E - 10.5'; Maple 4" - N72° W - 14.4'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 - Set M.P.O.L. between the N 1/4 Cor. and the N.E. Sec. Cor. of Section 3.
- 6 - Set at the computed center of the N.E. 1/4 of Sec. 3. Found iron rod set by Marquette Co. Rd. Comm. 13.5' N57° E from this Mon. Found error in Rd. Comm. computations plus incorrect method.
- 9 - Set M.P.O.L. between the East 1/4 Cor. and the Ctr. of Sec. 3. Found iron rod (bent) 14 Ft. N34° E from this Mon. Found error in Rd. Comm. computations plus incorrect method.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2 - 1" pipe, 4" aluminum cap; 8" B. Spruce - S20° W - 23.3'; 3" Cedar - N10° E - 20.9'; 8" B. Ash - N72° E - 15.1'; 3" Cedar - N29° W - 2.3'.
- 6- 1" pipe, 4" aluminum cap; 4" B. Spruce - S22° W - 36.1'; 16" B. Spruce - N8° E - 12.0'; 9" B. Spruce - S60° E - 8.6'; 12" B. Spruce - S80° W - 4.8'; Iron Rod - N57° E - 13.5'.
- 9 - 1" pipe, 4" aluminum cap; 4" Sugar Maple - N22° W - 10.9'; 8" Black Cherry - N71° E - 21.2'; 3" W. Spruce - S9° E - 15.6'; 3" Sugar Maple - N81° W - 34.1'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: