

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code *≠*

- | | | |
|---------------------------------------|---------------------------|--------------------------|
| 1. Public Land Survey | T <u>44N</u> R <u>24W</u> | <u>I-13, I-12, H-13.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 1/17/89, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-13. SE section corner of Section 34. Wood post, 1841, John Burt, D.S. Tamarack 10, N52E, 65 Lks.; Tamarack 10, N27W, 10 Lks.; Tamarack 9, S14E, 51 Lks.; Tamarack 11, S51W, 35 Lks.
- I-12. East 1/4 corner of Section 34. Wood post. A.D. Sullivan, 1852. Hemlock 15, N69E, 14 Lks. Birch 10, S68W, 25 Lks.
- H-13. South 1/4 corner of Section 34. Wood post, 1841, John Burt, D.S. Hemlock 14", N28E, 37 Lks.; DO 12, N59W, 44 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-13. Set by single proportionate measurement between the SW section corner of Section 34 and the SE section corner of Section 35. Many tam. stumps in the area but in very poor condition, could not identify any as OBT's.
- I-12. Set MPOL between the NE and SE section corners of Section 34. Could not identify OBT's.
- H-13. Set MPOL between the SW and SE section corners of Section 34. No sign of OBT's. Judging from the swamp calls the original 1/4 corner may have been a little north of this point but it is not definite enough to control. The cor. falls about 100' west of the west edge of open marsh in thick spruce and balsam.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--|--|---|
| I-13. DNR Monument.
6" cedar, S35W, 29.8'
5" cedar, N71W, 7.4'
5" cedar, N38E, 7.55'
4" cedar, S4E, 3.9' | I-12. DNR Monument
3" cedar, S21E, 15.6'
4" cedar, N89W, 20.0'
6" cedar, N13W, 34.3'
4" hemlock, N68E, 49.3' | I-13. DNR Monument.
4" bl. spruce, S7E, 14.0'
6" bl. spruce, N23E, 7.9'
4" balsam, N75W, 17.0'
3" balsam, S22W, 14.9' |
|--|--|---|

Signed by David B. Babbitt Date 3-21-89
 Surveyor's Michigan License No. 21558