

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located in:	Corner Code ##
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>G-8, J-5,</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 4/9/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-8. East 1/4 corner of Section 21. Mich. Cons. Dept., 1" pipe w/4" brass cap. 15" yellow birch, S35W, 8½ Lks. 15" yellow birch, N72W, 47 Lks.
- J-5. South 1/4 cor. of Section 11-½" iron pin, MDOT plans for M-35 FE Post, S27E, 04.34 6" tamarack, N05W, 54.79, 7" maple, N34W, 64.00.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-8. Found 1" pipe w/4" brass cap. Both Cons. Dept. NBT's are in place with bearings and distances as recorded but the SW one is a dead stub and the NW one has some dead limbs. The NW OBT is also in place and with one live limb but the lower face is completely rotted away. The upper face still has legible scribing but will soon also be rotted away. Re-witnessed monument as found.
- J-5. Found pipe from hot water tank driven in westerly ditch of Hwy. M-35. All Hwy. Dept. NBT's fall within construction area and were taken out by construction. ½" iron pin was apparently also removed by construction but the found pipe fits the position indicated on the Hwy. Dept. plans. Re-witnessed pipe as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|--|---|
| G-8. 1" pipe w/4" brass cap.
OBT 16" y.birch, N57W, 10.3'
7" hemlock, N2E, 21.8'
6" " , S72E, 28.2'
4" " , S6W, 26.4'
10" cedar, S78W, 35.7' | J-5. Pipe from hot water tank.

Nail & brass tag
in side of | { 4" tamarack, S9E, 49.1'
2" spruce, S20W, 22.75'
3" tamarack, N31W, 101.6'
Face of Conc. N84W, 14.0'
ROW Marker. |
|---|--|---|

Signed by David B. Babbitt Date 3-21-89
 Surveyor's Michigan License No. 21558