

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|--------------------|
| 1. Public Land Survey | T <u>44N</u> R <u>24W</u> | <u>G-13, F-13.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>33</u> T <u>44N</u> R <u>24W</u> | <u>15.</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 1/12, 1989, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13. SE section corner of Section 33. Wood post. 1841, John Burt, D.S. Tamarack 7, N42E, 72 lks.; Spruce 4, N43W, 6 lks.; Spruce 5, S28E, 11½ lks.; Spruce 4, S40W, 22 lks.
- F-13. South 1/4 corner of Section 33. Wood post, 1841, John Burt D.S. Spruce 4, N20W, 37 lks. DO 4, N42E, 86 lks.
15. W 1/16 corner on the south section line of Section 33. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13. Found stump of Northeast tamarack OBT definite hack mark and part of lower face. Scribing is burned off. Badly rotted and burned. Set mon. at record bearing and distance from stump.
- F-13. Set MPOL between the SW and SE section corners of Section 33. Corner falls in marsh with scattered scrub spruce and tamarack and an occasional scrub w. pine. No sign of OBT's.
15. Set MPOL between the south 1/4 corner and the SW section corner of Section 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|----------------------------|--------------------------|---------------------------|
| G-13. DNR Monument. | F-13. DNR Monument. | 15. DNR Monument. |
| 4" bl. spruce, N47E, 45.8' | 6" tamarack, N17E, 68.5' | 5" tamarack, N29W, 5.45' |
| 4" tamarack, S36E, 56.4' | 4" tamarack, N89E, 44.3' | 5" tamarack, N72W, 8.85' |
| 5" tamarack, S6E, 66.0' | 3" tamarack, S16E, 61.3' | 5" tamarack, S70W, 11.05' |
| 5" tamarack, N1W, 48.5' | 3" tamarack, N71W, 47.8' | 5" tamarack, S33E, 24.75' |

Signed by David B. Babbitt Date 3-21-89
 Surveyor's Michigan License No. 21558