

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>I-10, I-11.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 2/23/89, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-10. West 1/4 corner of Section 26. Wood post, A.D. Sullivan, 1852. Fir 8, S80E, 31 Lks.
 Hemlock 15, N59W, 14 Lks.
- I-11. SW section corner of Section 26. Wood post. 1852. A.D. Sullivan D.S.
 Sugar 17, N71W, 53 Lks.
 Fir 12, N69E, 45 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-10. Set MPOL between the SW and NW section corners of Section 26. Could not identify OBT's.
- I-11. Set in line with C of roads north and west and in line with old fence line south. Remains of very large tamarack stub showing hack marks on both north and south sides falls on line 663' S of cor. GLO. Record indicates a 17" tamarack line tree 657.4' south of this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| I-10. DNR Monument.
12" hemlock, N52E, 31.7'
5" hemlock, N4W, 11.5'
6" cedar, S55W, 24.1'
6" cedar, S40E, 35.1' | I-11. DNR Monument.
3" red pine, N47E, 71.6'
7" sugar maple, S38E, 62.5'
8" red pine, S63W, 154.7'
4" spruce, N71W, 134.7' |
|---|--|

Signed by David B. Babbitt Date 3-21-89
 Surveyor's Michigan License No. 21558