

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Marquette</u> <small>(County)</small>	Located in:	Corner Code <i>##</i>
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>K-11, L-11.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>36</u> T <u>44N</u> R <u>24W</u>	<u>1., 2.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

I, Keith Sackett, in a field survey on 8/27, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Not set on original survey nor subsequently apparently.
2. Not set on original survey nor subsequently apparently.

K-11. Original monument and accessories not found.  
 L-11. Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1. Established midway and online.
2. Established midway and online.

K-11. Restored by double proportion.  
 L-11. Restored midway and online.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1. DNR Monument	2. DNR Monument	K-11. DNR Monument	L-11. DNR Monument
8" cedar, N53E, 28.75'	8" cedar, N86E, 27.5'	9" hemlock, S30E, 38.2'	6" cedar, N62W, 32.0'
6" cedar, S70E, 34.5'	6" cedar, S24E, 26.85'	9" r.maple, N74E, 15.6'	10" cedar, S83E, 51.0'
5" cedar, S01E, 31.1'	10" hemlock, S30W, 26.4'	9" r.maple, N42W, 16.8'	6" cedar, N58E, 35.3'
9" cedar, S86W, 17.7'	12" cedar, N42W, 33.3'	8" h.maple, S62W, 35.4'	Sq. Post, NE 1.0'
			5" h.maple, S74W, 10.50'
			11" cedar, N3W, 20.46'
			9" cedar, S42E, 10.56'

Signed by Keith Sackett

Date 11-28-90

Surveyor's Michigan License No. 19006



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971  
 REVISED MAY 14, 1978  
 REVISED APR., 1983