

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code =#

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>24W</u> | <u>I-9.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, David B. Babbitt, in a field survey on 7/9, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-9. SE section corner of Section 22, Marquette County Road Commission -7-2-47- set 3/4" pipe "found cedar post & both OBT's".
 NBT's 7" cedar N76W, 18.9'
 8" elm N45E, 19.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9. Found 3/4" pipe fallen over in muck. Both County Road Commission OBT's in place, scribing visible on both but blazes in poor condition. The cedar is live and growing but the "elm" was really a black ash. It is down and in very poor condition. Reset pipe and set D.N.R. Monument beside it. There is a y. birch stump in the right position for the n.west OBT but it is too rotten to show any marks.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9. D.N.R. Monument
 6" cedar S83W, 30.55'
 5" cedar N22W, 25.15'
 5" cedar N80E, 25.35'
 4" cedar S10E, 41.7'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by David B. Babbitt Date 7-16-86

Surveyor's Michigan License No. RLS 21558