

RECEIVED

DEC 8 1989

RECREATION DIVISION
DEPT. OF NATURAL RESOURCES

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>14</u> T <u>44N</u> R <u>24W</u>	<u>16, 10.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 10/10, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

16. East 1/16 corner on the south section line of Section 14. No previous record.
10. South 1/16 corner on the west section line of Section 14. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

16. Set MPOL between the S $\frac{1}{4}$ corner and the SE section corner of Section 14. Found 3/4" pipe 28' N7 $^{\circ}$ E from this monument which may have been set by the Marquette Co. Road Commission but it is not properly located to be the 1/16 corner.
10. Set MPOL between the West 1/4 corner and the SW section corner of Section 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-------------------------------|------------------------|
| 16. DNR Monument | 10. DNR Monument |
| 5" black spruce, N26E, 24.75' | 5" cedar, N41E, 9.1' |
| 5" black spruce, N85E, 25.65' | 7" cedar, S29E, 11.15' |
| 6" black spruce, S5E, 29.6' | 8" cedar, S38W, 34.5' |
| 6" black spruce, N14W, 16.6' | 8" cedar, N24W, 14.15' |

Signed by David B. Babbitt Date 11-29-89
 Surveyor's Michigan License No. 21558