

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>F-11, G-12, E-12.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, in a field survey on 10/4, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-11. North 1/4 corner of Section 33. Wood post. A.D. Sullivan, DS, 1852, Hemlock 20, N8W, 32 lks
Cedar 9, S10E, 23 lks
- G-12. East 1/4 corner of Section 33. Wood post. A.D. Sullivan, DS, 1852, Spruce 4, N60W, 10 lks
DO 4, S74E, 26 lks
- E-12. West 1/4 corner of Section 33. Wood post. A.D. Sullivan, DS, 1852, Spruce 9, S84W, 26 lks
Cedar 14, N67E, 25 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-11. Set MPOL between the NE and NW section corners of Section 33. No original evidence found.
- G-12. Set MPOL between the NE and SE section corners of Section 33. No original evidence found.
- E-12. Set MPOL between the NW and SW section corners of Section 33. Found two old dead cedars one down and one standing that have blazes or axe marks facing this monument as set but they appear to have been marked after they were dead although one showed some evidence of older scarring, I could not identify it as the cedar OBT. If it was, it would make little difference in the position of this cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------|------------------------------|------------------------|
| F-11. DNR Monument (buried) | G-12. DNR Monument | E-12. DNR Monument |
| 7" twin maple, N22E, 26.3' | 4" black spruce, N33E, 30.6' | 7" cedar, S4E, 15.3' |
| 11" tamarack, S5W, 31.05' | 4" tamarack, S32E, 73.2' | 4" cedar, N68E, 11.1' |
| 6" cedar, S51W, 32.7' | 4" tamarack, N88W, 96.3' | 5" cedar, S63W, 27.25' |
| 16" w.pine, N70W, 51.3' | 4" black spruce, N6W, 34.65' | 5" cedar, S25W, 24.5' |

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558