

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>I-7, I-6.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 10/4/89, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-7. SW section corner of Section 14. Wood post. A.D. Sullivan, DS, 1852.
Tamarac 10, N38E, 54 lks., DO 10, N68W, 28 lks.
- I-6. West 1/4 corner of Section 14. Wood post, A.D. Sullivan, DS, 1852.
Birch 10, N78E, 25 lks., Hemlock 12, S74W, 15 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-7. Found old stake point with tam. stumps in place, bearings and distances exact, for both OBT's. Both stumps are in very poor condition and are too rotten to show any marks. Also found very old tam. stub 6' south of cor. with waist high blaze facing corner and very old tam. stub 38 ft. east of cor. with only the east side still standing which has a definite axe blaze for a line marking. G.L.O. record distances to edge of swamp 2.50 chs. west and top of hem. ridge 8.50 chs. east fit well.
- I-6. Set MPOL between the NW and SW section corners of Section 14. Could not locate OBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------|-----------------------------|
| I-7. DNR Monument | I-6. DNR Monument. |
| 4" cedar, N1W, 20.4' | 12" hemlock, N6E, 14.9' |
| 6" cedar, N85E, 12.05' | 8" sugar maple, S29W, 23.1' |
| 6" cedar, S38E, 24.25' | 5" hemlock, S77W, 42.35' |
| 4" cedar, N77W, 13.7' | 6" cedar, N75W, 31.5' |
| 4" cedar, S85W, 10.55' | |

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558