

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code ≠
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>K-7, L-9.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David Babbitt, In a field survey on 10/9, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-7.** NE section corner of Section 23, Marquette Co. Rd. Commission, about 1948 "Found very old cedar post, recognized cor.--set iron pipe." Balsam 7", N36E, 17.6'
 Balsam 9", N17W, 21.0'
- L-9.** South 1/4 corner of Section 24. Marquette Co. Rd. Commission, 1947. "Found old cedar with 1/4 mark scribed on it and remains of tamarack stumps that check for course and distance with original BT's. Set iron pipe and cedar post and new BT's".
 Maple 14", N55E, 22.7', Cedar 4", S36E, 29.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-7.** Found 3/4" pipe with both Marquette County Road Comm. witnesses in place but both are dead. This corner was not substantiated by original survey evidence but if there was a "very old cedar post" there in 1948, it seems reasonable to think that it dates back at least to the 1920's. The original survey record calls for leave swamp at 6.50 chs. enter swamp at 10:00 chs and stream 6 lks. at 12.57 going east from this cor. It calls for "1/2 acre of dry ground" at 7.73 chains south from this cor. and going north it calls for leaving the swamp at 2.00 chains. These feature calls all agree well with this location and since this location has apparently been accepted as the section corner for at least 60 to 80 years, I see no reason to dispute it. I have, therefore, re-witnessed the pipe as found.
- L-9.** Found 3/4" pipe with both Marquette Co. Rd. Commission wits in place but the maple is dead. Re-witnessed as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| K-7. 3/4" pipe.
10" cedar, S11W, 22.4'
13" cedar, N28W, 59.9'
(w/very crooked trunk)
6" cedar, N81E, 46.9'
13" cedar, S88E, 47.35' | L-9. 3/4" iron pipe.
8" cedar, N54E, 16.85'
Old NBT, 9" cedar, S25E, 29.5'
5" cedar, S48W, 26.85'
6" cedar, N66W, 42.7' |
|--|--|

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558