

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------------------|-------------|
| 1. Public Land Survey | T <u>44N</u> R <u>24W</u> | <u>G-9.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S <u>21</u> T <u>44N</u> R <u>24W</u> | <u>14.</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Dave Babbitt, in a field survey on 10/3, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

14. South 1/16 corner on the East section line of Section 21. No previous record.

G-9. SE section corner of Section 21. Wood post, A.D. Sullivan, D.S., 1852.
 Tamarac 11, N86E, 16 Lks.
 DO 14, S71W, 43 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

14. Set MPOL between the East 1/4 corner and the SE section corner of Section 21.

G-9. Found two old stake points in swamp muck under spagnum moss. Stump of S'west OBT in place flat axed blaze but no scribe marks visible. Roots of N'east OBT were also found at record bearing and distance but everything above ground is gone. An 11" cedar with waist high blaze facing corner bears S80E, 10.9' from corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

14. DNR Monument.
 white spruce, N31E, 11.65'
 8" cedar, S52E, 39.0'
 4" white spruce, S80W, 2.9'
 cedar, N8W, 27.85'

G-9. DNR Monument
 4" cedar, N36E, 19.9'
 5" cedar, S67E, 27.0'
 8" cedar, S14W, 27.9'
 4" cedar, N8W, 28.7'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Dave Babbitt

Date 11-28-89

Surveyor's Michigan License No. 21558