

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code \neq

- | | | |
|---------------------------------------|---------------------------------------|--------------------|
| 1. Public Land Survey | T <u>44N</u> R <u>24W</u> | <u>D-11, E-11.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S <u>29</u> T <u>44N</u> R <u>24W</u> | <u>16.</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 7/12, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-11. South 1/4 corner of Section 29. Wood post, A.D. Sullivan, D.S., 1852.
 Tamarac 20, N11E, 66lks. Spruce 7, N63E, 59 lks.
- E-11. Northwest section corner of Section 33. Wood post. A.D. Sullivan, D.S., 1852.
 Cedar 12, S84E, 33 lks. Hemlock 2, S51W, 44 lks.
16. East 1/16 corner on the South section line of Section 29. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-11. Set from large tamarack stump remains. Stump is very rotten and does not show any marks but it is the only tamarac near and using it as the tam. OBT. The 1/4 corner position fits the original survey record for leave stream 50 lks. East and center of stream 75 lks. west very well.
- E-11. Set by double proportion to the original survey record. Corner falls on the North edge of E-W road grade. OBT's not found.
16. Set MPOL between the South 1/4 corner and the SE section corner of Section 29.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|------------------------|------------------------------------|-----------------------|
| D-11. DNR Monument | E-11. DNR Monument (buried) | 16. DNR Monument |
| 7" cedar, N11E, 75.0' | 10" cedar, S44E, 77.8' | 5" cedar, N37W, 40.8' |
| 8" cedar, N6W, 70.6' | 7" cedar, S21E, 71.7' | 6" cedar, N35E, 11.6' |
| 6" cedar, S69W, 90.05' | 5" cedar, S50W, 45.75' | 6" cedar, S34E, 9.5' |
| 8" cedar, S6W, 84.3' | 3" apple, N41W, 23.35' | 6" cedar, S61W, 14.5' |
| | pk nail w/brass tag in butt blaze. | |

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558