

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code ≠#

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>24W</u> | <u>I-8, J-7.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property In Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Dave Babbitt, in a field survey on 9/27/, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8. West 1/4 corner of Section 23, wood post, 1852. Hemlock 16, S68E, 26 Lks.
 DO 13, N18W, 28 Lks.

J-7. North 1/4 corner of Section 23, wood post, A.D. Sullivan, D.S., 1852.
 Fir 10, S41W, 11 Lks.
 Hemlock 13, N57W, 21 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8. Set MPOL between the NW and SW section corners of Section 23. Could not identify OBT's.

J-7. Set MPOL between the NE and NW section corners of Section 23. Corner falls in old RR grade. Call for swamp edge 1 chain East in original survey notes fits well. No original evidence found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8. DNR Monument.	J-7. DNR Monument (buried)
8" spruce, N11E, 18.7'	6" black spruce, N44E, 75.9'
5" cedar, S22W, 21.4'	6" hemlock, N70E, 56.0'
7" cedar, S68W, 26.55'	8" sugar maple, S19W, 40.35'
4" balsam, N58W, 21.3'	8" black spruce, N60W, 30.5'

Signed by David B. Babbitt

Date 11-28-89

Surveyor's Michigan License No. 21558