

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>10.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>33</u> T <u>44N</u> R <u>24W</u>	<u>10, 14,</u>
	S <u>28</u> T <u>44N</u> R <u>24W</u>	<u>7.</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 10/4, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 10. South 1/16 corner on the west section line of Section 33. No previous record.
- 14. South 1/16 corner on the east section line of Section 33. No previous record.
- 7. North 1/16 corner on the east section line of Section 28. No previous record.
- 10. South 1/16 corner on the west section line of Section 28. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 10. Set MPOL between the west 1/4 corner and the SW section corner of Section 33.
- 14. Set MPOL between the east 1/4 corner and the SE section corner of Section 33.
- 28. Set MPOL between the east 1/4 corner and the SE section corner of Section 28.
- 10. Corner set MPOL between SW corner and west 1/4 corner of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-------------------------|-------------------------------|------------------------------|
| 10. DNR Monument. | 14. DNR Monument. | 7. DNR Monument. |
| 4" cedar, S78E, 30.9' | 4" black spruce, N19E, 15.1' | 14" cedar, N55E, 30.8' |
| 8" hemlock, S17E, 44.1' | 6" tamarack, S5E, 20.4' | 7" yellow birch, S49E, 19.6' |
| 5" bl. ash, N9E, 22.5' | 4" black spruce, N69W, 21.75' | 6" black ash, S88W, 23.9' |
| 8" maple, N36E, 31.9' | 5" black spruce, N32W, 29.8' | 9" cedar, N2E, 30.55' |
-
- 10. DNR Monument.
 - 5" cedar, N66E, 33.55'
 - 8" cedar, S40E, 13.5'
 - 11" cedar, S66W, 15.0'
 - 8" cedar, N55W, 8.8'

Signed by David B. Babbitt Date 2-21-90
 Surveyor's Michigan License No. 21558