

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T <u>44N</u> R <u>24W</u>	<u>1, 3, 14.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 10/23, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- West 1/16 corner on the north section line of Section 14. No previous record.
- North 1/16 corner on the west section line of Section 33. No previous record.
- South 1/16 corner on the east section line of Section 28. No previous record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- Corner set MPOL between northwest corner and north 1/4 corner of Section 14.
- Corner set MPOL between northwest corner and west 1/4 corner of Section 33.
- Corner set MPOL between southeast corner and east 1/4 corner of Section 28.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                              |                       |                            |
|------------------------------|-----------------------|----------------------------|
| 1. DNR Monument              | 3. DNR Monument.      | 14. DNR Monument.          |
| 8" tamarack, N42E, 31.0'     | 6" cedar, N69E, 15.9' | 8" twin cedar, N42E, 24.0' |
| 8" tamarack, S74E, 4.35'     | 5" cedar, S32E, 9.65' | 7" cedar, S30E, 9.3'       |
| 9" white pine, S4E, 35.7'    | 6" cedar, S28W, 4.95' | 9" cedar, S41W, 17.9'      |
| 6" black spruce, S85W, 23.2' | 8" cedar, N17W, 3.75' | 7" cedar, N67W, 7.7'       |

Signed by David B. Babbitt Date 2-21-90  
 Surveyor's Michigan License No. 21558