

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 25 W. .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 4 and 9

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 6" Cedar S 18° E 36 links

16" Power Pole N 80° W 43 links

Marked "B.T." - 5" Cedar S 36° E 10 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two original Cedar B.T.'s in good condition.

Corner lies on East edge of power line clearing.

Corner shown to us by Arne Metsa, District Forester.

Corner has been perpetuated by unknown surveyor.

Corner placed and witnessed June 25, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 6/28/56
REGISTERED LAND SURVEYOR