

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 25. W.

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 29, 30 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 36" W. Pine stump - S 15 E - 19 Links -----

6" W. Pine - N 85 W - 22 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Burned over area, no original evidence.

Corner was placed and witnessed April 23, 1952

SURVEYORS SEAL

SIGNED Sean C. DeLoe
REGISTERED LAND SURVEYOR

DATE 6/23/52 -