

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 25 W. . .

Marquette

COUNTY

DESCRIPTION OF CORNER Meander Corner between Sections 9, 16 on right bank  
of Escanaba River  
DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 10" Cedar N 44° W 18 1/2 links  
"M. C. NBT"  
13" Cedar N 55° E 19 links  
"M. C. NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Replaced meander corner from one Cedar B.T. in excellent condition. 18"  
Cedar is stump out high with all scribe marks plain. B.T. bears S 6° W 81 links.  
No evidence of other Cedar B.T.

Meander Corner found by Arne Metsa, District Forester, by using hand compass  
and pacing.

No evidence of use at this meander corner.

Corner placed and witnessed 1-25-57.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2-7-57  
REGISTERED LAND SURVEYOR