

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

MARQUETTE

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> ^{<u>42</u>} S., R. <u>25</u> ^{<u>X</u>} E. W.	A-10, A-12
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	, T. <u>44</u> ^{<u>42</u>} S., R. <u>25</u> ^{<u>X</u>} E. W.	3, 10
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

Frank J. Bray

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on May 21 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- A-10 Woodpost:**
Cedar 7" S44°E 18 links
Spruce 9" N73°W 15 links
- A-12 Woodpost:**
Sugar 10" N60°E 26 links
Sugar 10" N18°W 47 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-10** This corner was placed midway and on line between the section corners ½ mile to north and to south. No original evidence found.
- A-12** This corner was replaced from government notes noting 4 foot boulder 6 links west of ¼ post.
- 3** This corner was placed midway and on line between the section corner to the north and ¼ corner to the south.
- 10** This corner was placed midway and on line between the ¼ corner to the north and town corner to the south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
All: 1" iron pipe with 4" aluminum cap. All Bearings are magnetic.

- A-10** 10" Cedar (¼S) (NBT) N21°E 24.5'
6" Cedar (¼S) (NBT) N53°W 25.1'
- A-12** 6" H. Maple (¼S) (NBT) N80°W 11.9'
6" H. Maple (¼S) (NBT) N52°E 12.6'
- 3** 12" Cedar (N 1/16) (BT) N15°W 16.7'
6" R. Maple (N 1/16) (BT) S74°E 26.0'
- 10** 8" Cedar (S 1/16) (BT) N12°W 2.7'
12" Cedar (S 1/16) (BT) S69°E 11.6'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Frank J. Bray CHIEF OF SURVEY PARTY DATE 6-10-74
(Frank J. Bray) MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

13575

SURVEYOR'S MICHIGAN REGISTRATION NO. _____