

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 44 <del>XX</del> N. R. 25 <del>XX</del> W.	F-3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 29, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

North 1/4 corner of Sec. 9

Mich. Dept. of Conservation

1" pipe with 4" brass cap 6-28-56

Replaced 1/4 corner from two original cedar B.T.s in good condition.

6" cedar - S18<sup>0</sup>E - 36 Lks.

16" power pole - N80<sup>0</sup>W - 43 Lks.

Market "B.T." 5" cedar - S36<sup>0</sup>E - 10 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-witnessed Cons. Dept. mon. as found. The cap is aluminum not brass. All of the N.B.T.s marked in 1956 have been cut including the 16" power pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe w/4" aluminum cap.

6" cedar - N84<sup>0</sup>E - 95.9'

P1. R LS Cap in

face of P.P. S50<sup>0</sup>E - 23.3'

5" cedar - S52<sup>0</sup>W - 72.5'

Pk. nail in

face of P.P. N77<sup>0</sup>W - 25.2'

SIGNED BY

*David B. Babbitt*

DATE

9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)