

MAR 20 1999

MARQUETTE COUNTY MICHIGAN RECEIVED FOR RECORD

1998 DEC 16 PM 3:21

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Patricia L. Monkey REGISTER OF DEEDS

For corners in MARQUETTE (County) Located In: Corner Code # 1. Public Land Survey T 45N R 25W F-13 T 44N R 25W F-1 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims

LIBER R2 PAGE 77

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on APRIL 30th, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column F and row 13.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: F-13: Quarter Corner common to Section 33, T45N-R25W; and Section 4, T44N-R25W. 1844: William A. Burt's original survey notes describe the corner monument as a Cedar post referenced by: 7" Tamarack N75E, 12 L

1982: A Certificate of Survey by Gerald W. Carlson P.S. #24589 for the Minatome Corporation (No Liber and page given) indicates the corner as a monumented corner. Distance N89-48'-13"E, 2633.16' to the S.E. Corner of Section 33, and Distance S89-48'-13"W, 2633.16' to the S.W. Corner of Section 33. No accessories given.

1983: A Certificate of Survey recorded by Gerald W. Carlson P.S.#24589 in L. 001, S.M. pp. 443-444, indicates the corner as a set 5/8" X 18" rebar with RLS cap midway between the S.E. and S.W. Corners of Section 33. Distance N89-48'-13"E, 2633.16' to the S.E. Corner of Section 33, and Distance S89-48'-13"W, 2633.16' to the S.W. Corner of Section 33. Referenced to d.h. nails in: 6" W. Birch S28W, 26.00' 6" Spruce S73W, 23.73' 7" W. Birch N30W, 40.93' Easterly Power Pole, Double Set of Power Poles N23E, 79.03' (SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: F-13: 1998: No original corner evidence found. Found and accepted a 5/8" Iron with MEI #24589 Cap, 8.5' E. of West end of steel post fence line with barbed wire - at W. edge of powerline clearing. Bearings and distances to remaining 2 found witnesses check very well with those recorded in L. 001, SM pp. 443-444, and L. 5, RC Pg. 259. Checked Line Call:(Leave Swamp Course N. & S., West 9.50 chains [627'] from corner. Measured Call: West, 600', Leave Swamp Course N. & S.. Distance East is 2632.90. Distance West is 2633.29.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: F-13: 1998: Replaced found cap and iron with a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner. Monument is 0.45' above ground. Measured to set d.h. nails in existing references: 8" Spruce S78W, 23.74' (Carlson NBT) 8" W. Birch N31W, 40.98'(Carlson NBT) Established new references: 6" Spruce S03W, 58.94' 5" Spruce N06W, 30.43' Orange Steel Sign Post w/ Yellow Survey Marker Sign N82W, 4.1'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

RATIFIED BY PEER GROUP P.A. 345 OF 1990 Gary J. B... DATE Nov 2, 1998



Signed by Gerald W. Carlson Date 12-14-98 Surveyor's Michigan License No. 24589

