

MAR 16 1999

SECTION

G-13:

PART A CONTINUED:

No Date: M.C.R.C. Government Corner Index Book #641 indicates the corner as an Old Cedar Post. No accessories given.

No Date: M.C.R.C. Government Corner Index Book #643 indicates the corner as a Squared Spruce Post. No accessories given.

1982: A Certificate of Survey by Gerald W. Carlson P.S. #24589 for Minatome Corporation (No Liber or pg. given) indicates the corner as a monumented corner. Distance N89-06'-46"E, 2676.24' to the South 1/4 Corner of Section 34. Distance S89-48'-13"W, 2633.16' to the South 1/4 Corner of Section 33. No accessories given.

1982: An LCRC recorded by Gerald W. Carlson P.S. #24589 in L. 5, RC Pg. 40, indicates the corner as a found 1" Pipe, 15" high, and a 4-way blazed tree w/location tag. Set a 2"x2"x4' stake alongside pipe. Referenced by:

6" J. Pine	N70W,	15.00'	6" J. Pine	N07E,	22.09'
8" J. Pine	N71E,	14.82'	5" J. Pine	S15E,	15.76'

1983: A Certificate of Survey recorded by Gerald W. Carlson P.S. #24589 in L. 001, SM Pg. 443, indicates the corner as a found 1" Pipe, 15" high, and location tag. Distance N00-06'-27"E, 2638.38' to the East 1/4 Corner of Section 33. Referenced by d.h. nails in:

6" J. Pine	N70W,	15.00'	6" J. Pine	N07E,	22.09'
8" J. Pine	N71E,	14.82'	5" J. Pine	S15E,	15.76'

1989: The corner is shown on an Easement Description Map for Wisconsin Electric recorded by Gerald W. Carlson P.S. #24589 in L. 129, MR Pg. 344. No description of corner object or accessories given.