

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 26. W.

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 11, 12, 13, 14 . . .

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 10" Cedar = S 43 W = 50 Links -----

12" Cedar = N 41 W = 79 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. Original corner  $\frac{1}{4}$  mile East, swamp edges North and West.

Corner was placed and witnessed November 5, 1952.

SURVEYORS SEAL

SIGNED

*James C. De Meter*  
REGISTERED LAND SURVEYOR

DATE 3/25/53