

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44. NR. 26. W.

Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 20, 21, 28, 29

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER 14" W. Birch - N 80 W - 21 Links

8" S. Maple - S 50 E - 80 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. One probable B.T. in place, badly rotted.

Corner was placed and witnessed April 23, 1952.

SURVEYORS SEAL

SIGNED

John C. L. Miller
REGISTERED LAND SURVEYOR

DATE

6/23/52