

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 26 W.

Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 22 & 23

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER

10" Spruce - N 80 W - 33 Links

6" Spruce - S 6 W - 39 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew, while making a partial resurvey of this Township. In the absence of any definite original evidence, corner was placed in line, and at a proportionate distance between the Section corners.

Corner was placed and witnessed November 10, 1953.

SURVEYORS SEAL

SIGNED John C. [Signature] DATE 9/2/56  
REGISTERED LAND SURVEYOR