

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR 26 W

Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 25, 26, 35, 36

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER	4" Cedar	N 33° E	53½ links
	"S 25 NBT"		
	6" Cedar	N 5° W	61½ links
	"S 26 NBT"		
	7" B. Spruce	S 26° W	43½ links
	"S 35 NBT"		

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one tamarack B.T. in place in good condition.

Two Tamarack trees with Section Numbers scribed on face about 3 ft. above ground. (Believe these trees were marked by the inspecting Deputy Surveyor within a few years of the Original Survey. Age of tree agrees with this.)

Corner found by Arne Metsa, District Forester, while cruising timber.

Corner placed and witnessed 1/18/57.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2-7-57  
REGISTERED LAND SURVEYOR