

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 N.R.'s. 26 & 27 W.

Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 18, 19, 22, and 24

CORNER MONUMENT 1 inch galvanized pipe with 4 inch brass cap


DATE MONUMENT PLACED AND WITNESSED April 26, 1961

WITNESSES TO CORNER..... 8" White Pine S 60 W 35. links

8" Soft Maple N 19 E 23.5 links

12" White Pine S 88 E 65.5 links

AND



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set from original w. pine bearing trees. One pine tree broken off near ground level, has been down for a long time and fallen in direction so face was down. After removing all dead wood I uncovered old face from underneath. Face was very definite, charred by fire, with a few shallow axe marks of a later date. The other pine was a stump, the outside of which was badly rotted and decayed. Stumps fit the original field notes in species, size, bearings, and distance. The spruce and fir bearing trees have completely disappeared. Corner was located by A. Metsa on November 5, 1960. Corner was set by A. Metsa and R. Bols on April 26, 1961.

SURVEYOR'S SEAL

SIGNED

A. Metsa
REGISTERED LAND SURVEYOR

DATE

5/1/61