

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 N.R. 26 W.


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 35 and 36

CORNER MONUMENT 1 inch galvanized pipe with 4 inch brass cap.

DATE MONUMENT PLACED AND WITNESSED 4/18/61

WITNESSES TO CORNER.....



Sugar Maple 8 S22W 47 Links

Sugar Maple 6 N63W 36 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located by pacing and hand compassing down section line from original NT corner 1/2 mile to north. Two birch bearing trees remain. One is a stump saved at 4 1/2 ft. height, quite badly rotted, but hard slab recovered from duff at base of stump, facing corner, showed distinct face but no scribe marks. The other NT is a down, badly rotted birch tree. The two birches fit the original notes in size, bearing, and distance. At the proper location dug up an old squared post, down, and buried in leaves. Corner set from birch bearing trees on 4/18/61 by A. Neta and Mr. Oliver.

SURVEYOR'S SEAL

SIGNED

A. Neta  
REGISTERED LAND SURVEYOR

DATE

4/24/61