

OK DB.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located in:	Corner Code \neq
1. Public Land Survey	T <u>44N</u> R <u>26W</u>	<u>I-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>3</u> T <u>44N</u> R <u>26W</u>	<u>7.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David Babbitt, in a field survey on 5/28/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1. NE section corner of Section 3. Mich. Dept. of Conservation, 1952. 1" pipe w/4" brass cap, set from one OBT stream crossing 56 Lks. south & 65 Lks. east O.K. 12" cedar, S76W, 19 Lks. 10" cedar, N86E, 85 Lks.

7. North 1/16 corner on the east section line of Section 3. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1. Found brass capped Cons. Dept. monument on north side of small stream. 12" cedar NBT S76W, 19 Lks. was blown down on top of monument. SE NBT not found. Cut part of blown down cedar away from mon. - straightened it up and marked 4 new NBT's.

7. Set by single proportion to the GLO record between the east 1/4 corner and the NE section corner of Section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------------|------------------------|
| I-1. 1" pipe w/4" brass cap. | 7. DNR Monument. |
| 8" cedar, S60E, 63.0' | 3" spruce, S33E, 11.5' |
| 7" cedar, S10E, 66.2' | 5" maple, S27E, 17.7' |
| 11" cedar, S59W, 86.7' | 5" spruce, N89W, 14.8' |
| 8" cedar, N47W, 62.7' | 9" maple, N31W, 22.3' |

Signed by David B. Babbitt Date 8-1-88
Surveyor's Michigan License No. 21558