

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 44 N. S. R. 30 ^{XX} W.	M1
2. PROPERTY CONTROLLING IN SECTION <u>1</u> , T. 44 N. S. R. 30 ^{XX} W.		2
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 27, 1974, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner M1 - Sec. Cor. 1, 6, 31, & 36, T44-45N, R29-30W:
 Wood post (Not found. Found a monument described below.)
 W. Pine 20 N56W 21 (" " No subsequent accessories found.)
 W. Pine 22 S56E 23 (" " " " " ")

Corner 2: W 1/16 cor. bet. Sec. 1 & 36, T44-45N, R30W:
 Not established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner M1: Re-established proportionately on line between original Sec. Cor. 79.538 ch. E and original 1/4 cor. 39.984 ch. W. Corner thus set falls 79.873 ch. N of original corner to S, record being 79.85 ch. Found a 1 1/2"x6' iron pipe purporting to be this corner N9°47'E 28.62 ft., probably set by Mich. State Highway Dept. by traverse sometime in the 1930's. No evidence that it is original and its mis-alinement with the original corners noted above, for no evident reason, causes the undersigned to discount it as accurately representing the original corner position.

Corner 2: Established on line between Sec. Cor. 19.992 ch. E and 1/4 cor. 19.992 ch. W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner M1: 1" I.D. x 42" iron pipe with 4" brass cap.
 Red Pine 12 N45°E (mag.) 92.6 ft. "S31, NBT"
 White Spruce 6 S34°E (mag.) 36.1 ft. "S6, NBT"
 1 1/2"x6' iron pipe N9°47'E 28.62 ft. "Witness Monument")

Corner 2: 1" I.D. x 36" iron pipe with 4" aluminum cap.
 W. Pine stump 32 S54°E (mag.) 27.7 ft. "1/16S, BT"
 Aspen 8 N31°W (mag.) 14.6 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE November 21, 1975
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

