

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 44 N.R. 30W


Dickinson COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 24 and 25.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 4-25-63

WITNESSES TO CORNER..... 6" Hard Maple (¼ S. N.B.T.) N. 70° E., 33 Lks.



6" Hard Maple (¼ S. N.B.T.) S. 39° E., 65 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established on line and by proportionate distance bet. a good Sec. Cor. 39.91½ Chs. East and a 72" W. Pine Line tree 25.29½ Chs. West.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10/7/63  
REGISTERED LAND SURVEYOR