

Lansing

✓

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette-Dickinson COUNTY


T 44-45 N R 30 W

DESCRIPTION OF CORNER 1/4 corner between Sections 6 and 31

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 7, 1968

WITNESSES TO CORNER..... White Spruce 10 S9°E 106 1/2 lks. "1/4 S NBT"



White Spruce 24 N8°E 162 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner set by proportionate measurement on line between Section Corner 40.01 chains East and Section Corner 38.57 chains West. No evidence or original corner or its accessories and found no replacement monuments or accessories.

Corner is buried in an E and W county road, toward south edge of improved portion of road.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 2/14/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing