

Lansing

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette-Dickinson COUNTY


T 44-45 N R 30 W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 10, 1968

WITNESSES TO CORNER..... Sugar Maple 10 N65°W 80 lks. "1/4 S NBT"



Sugar Maple 6 S23 1/2°E 14 lks. "1/4 S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of an old 3"x3"x30" squared wood post purporting to be the above corner. Position had been rewitnessed 20-30 years ago with a Basswood 7 N5°E 28 lks. and a Basswood 10 N39°W 35 lks., by unknown surveyor. Calotex location tag bearing date 5/1/57 is on nearby tree. Position has apparently been used as the corner by adjacent landowners for many years.

Corner is not on line between section corners to east and west. Proceeding westerly from NE corner of Sec. 5, there is a deflection of 1°02' to the right at the 1/4 corner in order to fall at the NW corner of Sec. 5. Midway position on true line between the section corners lies about 36.3 links north and 1.9 links west of the position recorded herein.

As no evidence of the original monument or its accessories was identified, the wood post was reluctantly perpetuated by the undersigned.

Variation at this corner is about 2°15' West.

SURVEYOR'S SEAL

SIGNED Arthur D. Enger DATE 2/14/69
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing