

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette-Dickinson COUNTY


T 44-45N R 30W

DESCRIPTION OF CORNER East 1/16 corner between Sections 5 and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 4, 1968

WITNESSES TO CORNER..... Sugar Maple 5 S27°W 6 lks. "1/16 S BT"



Sugar Maple 5 N78°E 22½ lks. "1/16 S BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established midway on line between Section Corner 20.11 chains east and 1/4 corner 20.11 chains west. Found a rotted 1" picket lying on the ground, which apparently had stood about N26°W 12½ lks. from corner established here. Picket set by unknown surveyor. Also some blazed trees in vicinity.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

3/19/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68