

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette-Dickinson COUNTY


T 44-45N R 30W

DESCRIPTION OF CORNER Section Corner 5, 6, 31, and 32

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 4, 1968

WITNESSES TO CORNER..... White Birch 10 (West one of twins) N46°E 296½ lks. "S32 NBT"



No others available

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established from one probable original BT stump, a W. Pine 22 N46°E 297 lks. BT is now a badly rotted stump with no marks, but the corner position as set from it checks quite well with a section corner 80.44 chains east and the township corner 78.58 chains west, and with marsh edges to east and west mentioned in original field notes. The W. Pine stump thought to be an original BT lies on the edge of a narrow point of upland projecting into the marsh and is about the only place such a tree was likely to have grown.

Corner is in a wet, brushy marsh. Found no evidence of any other corner post in the vicinity.

SURVEYOR'S SEAL

SIGNED

Arthur D. Enger
REGISTERED LAND SURVEYOR

DATE

3/19/69

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68