

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Iron-Dickinson COUNTY


T 44N R 30-31W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 6

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 8, 1968

WITNESSES TO CORNER..... Jack Pine 10 S45°E 44 lks. "1/4S NBT"



Jack Pine 8 N78°W 83 lks. "1/4S NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement between an original section corner 39.95 chains south and a re-established township corner 40.60 chains north. Land has been heavily burned over; found no evidence of original corner or its accessories or of any replacement monument or accessories.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

3/19/69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68