

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 45 N.R. 23 W


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner for Sections 16-17-20-21

CORNER MONUMENT 1" Pipe with 1/4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3-13-62 with A. Metsa, District Forester

WITNESSES TO CORNER..... 9" Soft Maple (S 21 NBT) S 80° E 39 links



8" Soft Maple Twin (S 16 NBT) N 27° E 60 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two original B.T.'s. A Y. Birch (green) bearing S  $42\frac{1}{2}^\circ$  W 15 links and a Hemlock stub bearing N  $45^\circ$  E 08 links. Hemlock tree lying on ground with upper face and scribe marks in good condition.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 10-28-63  
REGISTERED LAND SURVEYOR  
Billy D. Buckler